

WHAT IS CLAIMED IS:

1. A cable management system, comprising:

a patch panel having a first connectivity interface configured to connect with cables; and

a wire manager located proximate said patch panel, said wire manager having a body with a curved interior contour, said wire manager being oriented in a non-orthogonal relation to said patch panel such that said body extends at a non-orthogonal angle from said first connectivity interface.
2. The cable management system of claim 1, wherein said patch panel and said wire manager extend along a common non-linear path.
3. The cable management system of claim 1, wherein said patch panel and wire manager extend along a common circular arc.
4. The cable management system of claim 1, further comprising a pair of wire managers mounted on opposite sides of said patch panel, said pair of wire managers and said patch panel forming a C-shape.
5. The cable management system of claim 1, wherein said patch panel and wire manager are joined to one another to be free-standing independent of a frame.
6. The cable management system of claim 1, wherein said wire manager and patch panel include adjoining sides that abut against one another, said adjoining sides extending along a radial axis through a center of the cable management system.
7. The cable management system of claim 1, wherein said body of said wire manager includes a convex back wall that bows into an interior cavity of said body.

8. The cable management system of claim 1, wherein said body of said wire manager includes back, side and front walls formed integral with one another, said side walls flaring outward from one another as said side walls extend from said back wall toward said front wall.

9. The cable management system of claim 1, wherein said body includes walls surrounding a cavity configured to hold cables, said walls having an semi-circular interior contour.

10. The cable management system of claim 1, further comprising a plurality of patch panels stacked on one another and first and second stacks of said wire managers provided along opposite sides of said plurality of patch panels.

11. The cable management system of claim 1, further comprising a plurality of said wire managers, each wire manager including a mounting post projecting transversely in one direction from said body and a post receptacle opening transversely in an opposite second direction from said body, said mounting posts and post receptacles on adjacent being configured to mate when said plurality of said wire managers are stacked on one another.

12. The cable management system of claim 1, further comprising a frame, at least one of said patch panel and wire manager being mounted to said frame.

13. The cable management system of claim 1, further comprising a frame extending upward through said wire manager, wire manager being secured to said frame.

14. A wire manager for retaining cables in a cable management system having a front face, said wire manager comprising:

side walls, at least one of said side walls being configured to be located proximate a front

face of the cable management system;

a front wall joined to said side walls; and

a back wall joined to said side walls, said front, back and side walls surrounding a cavity having a curved interior contour, said front and back walls extending at non-orthogonal angles from said side wall located proximate the front face such that said front and back walls extend at a non-orthogonal angle from the front face when the wire manager is located proximate the front face.

15. The wire manager of claim 14, wherein said front, back and side walls form a semi-circular interior contour about said cavity.

16. The wire manager of claim 14, wherein said side wall proximate the front face extends along a radial axis outward from a center of the cable management system.

17. The wire manager of claim 14, wherein said back wall is convex and bows into said cavity.

18. The wire manager of claim 14, wherein said back, side and front walls are formed integral with one another.

19. The wire manager of claim 14, wherein said side walls flare outward from one another as said side walls extend from said back wall toward said front wall.

20. The wire manager of claim 14, wherein at least one of said front, back and side walls further comprises a mounting post projecting transversely in one direction there from and a post receptacle opening transversely in an opposite second direction there from, said mounting

post and post receptacle being configured to mate on adjoining wire managers when a plurality of wire managers are stacked on one another.

21. The wire manager of claim 14, further comprising a bracket on one of said side walls, said bracket being configured to be secured to a frame.

22. The wire manager of claim 14, further comprising an opening through one of said front, back and side walls to receive cables.